No.	Items of work	Unit	Rate	Quantity	Rate quoted in	
					Figures	Words
			Rs. a. p.		Rs. a. p.	Rs.
5	Earthwork to breach filling including lead, lift and consolidation	C.yd.	0 6 0	3,032		
6	Sand and silt removal in the breached gap with necessary lead and lift	,,	0 3 0	1,786		
7	Puddle wall (clay mixed with gravel) ..	,,	0 8 0	525		
8	Jelly drain in the breached gap ..	,,	0 8 0	50		
9	Turfing the slopes and watering till it is satisfactory	S.yd.	0 1 0	4,005		
10	New rough stone revetment with jelly backing and jelly wedging including necessary lead and lift	C.yd.	1 12 0	1,453		
11	Dismantling the old stone work, etc. ..	,,	0 4 0	200		
12	Old rough stone revetment with new jelly wedging and jelly backing including lead and lift	,,	0 12 0	150		
13	Gravel backing with necessary lead and lift	C.yd.	0 6 0	459		
14	Providing new grade stones at bed slabs including carving figures and painting	Each	2 0 0	17		
15	Providing Index Stones	,,	0 6 0	17		
16	Providing and fixing Reg. No. stone on bed slab including figuring and painting ..	,,	5 0 0	1		
17	Providing and fixing B. M. stones on bed slabs including figuring and painting	,,	3 0 0	2		
18	Providing gauge stone on bed slab, with necessary masonry works, figuring and painting, etc.	,,	15 0 0	1		
	Waste weir.					
1	Earthwork excavation for foundation ..	C.yd.	0 3 6	131		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	191		
3	Burnt brick in surki mortar	,,	0 4 6	906		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar bed, etc. ..	S.ft.	0 6 0	471		
5	Plastering with surki mortar	Sqr.	3 8 0	10·58		
6	Joggle joints for coping slabs	Each	1 0 0	13		
7	Rough stone apron with jelly backing and jelly wedging including lead and lift, etc.	C.yd.	1 12 0	62		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 16th January 1939.

The attention of the public is invited to the detailed notification, dated 13th January 1939, published on pages 156-159 Part VI of the *Mysore Gazette*, dated 19th January 1939, regarding tenders for the Restoration of Vokkaleri Hirekere Major Tank, Register No. 204—84 of Kolar Taluk.

The last date for receiving tenders is 8th February 1939 up to 12 Noon.

Abstract Noification dated 16th January 1939.

The attention of the public is invited to the detailed notification, dated 12th January 1939, published on pages 159-162 of Part VI the *Mysore Gazette*, dated 19th January 1939, regarding tenders for the construction of Hostel Buildings attached to the Agricultural Middle School at Kagathi in Chintamani Taluk.

The last date for receiving tenders is 8th February 1939 up to 12 Noon.

R. TIPPAIYA,
Executive Engineer.